

NOTE - Quantities are an estimate only and are not to be used for determining pricing or payments

Summary Table for Clay Quantity	
Description	Volume (m3)
Clay Underside of Asphalt Road	752.6
Clay Underside of Grass/Topsoil	424.8
Clay Underside of Concrete Walkway	176.6
Total Clay (m3)	1354.0

Summary Table for Gravel Quantity	
Description	Volume (m3)
Gravel behind Retaining Wall	67.3
Gravel Underside Concrete Walkway	6.7
Total Gravel (m3)	74


Clay underside of Concrete Slab = 176.6  
Gravel underside of Conc Slab = 6.7

Gravel Behind Retaining Wall = 67.3

Clay underside of Asphalt Road = 752.6 m3

Clay underside of Grass/Topsoil = 424.8

#### LEGEND




#### NOTES:

- UTILITIES TO BE SUPPLIED AND INSTALLED IN COMPLIANCE WITH STRATHCONA COUNTY REGIONAL CONSTRUCTION STANDARDS.
- NURSERY GROWN, MIN. 20% HERC RESCUE, 20% CHEWING FESCUE, 20% CREEPING FESCUE, AND 20% ROCKY MOUNTAIN FESCUE BLENDED EQUALLY, OF CERTIFIED CANADIAN, 1" BEECH P AVAILABLE LOCALLY.
- TRANSFORMER PAD DIMENSIONS SHOWN AS APPROXIMATE. ACTUAL DIMENSIONS TO BE CONFIRMED DURING SHOP DRAWING REVIEW.
- PROVIDE OUTDOOR PANEL SIGN ON CHAIN LINK FENCE IN ACCORDANCE WITH STRATHCONA COUNTY VISUAL IDENTITY MANUAL (SECTION 3.3) AND LANDSCAPE SIGNAGE. TEXT ON SIGN TO INCLUDE FACILITY NAME, BUILDING ADDRESS, AND "STRATHCONA COUNTY UTILITIES CONTACT NUMBER: 180-467-7766 AND NO TRESPASSING" STATEMENT.

NOTE: THIS DRAWING IS HALF SCALE WHEN PRINTED TO 11" x 17" FORMAT

FOR APPROVAL

No.	DESCRIPTION	BY	DATE
2	FOR APPROVAL	SM	Jan. 6, 2023
1	FOR APPROVAL	SM	Nov. 23, 2022



Scale 1:100  
0 1 2 3 4m



MATTAMY (SHERWOOD PARK) LTD

HEARTHSTONE SANITARY LIFT STATION

Drawn: AL Design Checked: SM Date: Nov. 23, 2022  
Designed: SM Discipline Review: JRK Date: Nov. 23, 2022

SITE WORKS  
PROPOSED SITE PLAN

Drawing No.  
15719  
SW  
101  
Sheet No.  
101